BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer, Project Division, B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of Work: Construction of Samudhaya Bhavana and Gym at Yelahanka Old Town in ward No.01

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
1	9.00	KSRRB M200-12.2. Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. i) Lime /Cement Concrete. I. By Manual Means :B. Cement Concrete Grade M-15 & M-20. with all lead and lift and directions of the Engineer in charge of the work	Sqm	370.00	Three Hundred Seventy Rupees and Zero Paise
2	6.75	KSRRB M200-12.1.Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications.Prestressed / Reinforced cement concrete grade M-20 & above. with all lead and lift and directions of the Engineer in charge of the work	Cum	900.00	Nine Hundred Rupees and Zero Paise
3	187.50	Dismantling Mangalore tiles roof and stacking the material within a radius of 50 meters.with reepers with all lead and lift and directions of the Engineer in charge of the work	Sqm	50.00	Fifty Rupees and Zero Paise
4	4.95	KSRRB M200-16KSRRB M200-12.1.Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffoldingwherever necessary, sorting the dismantled material, disposal ofunserviceable material and stacking the serviceable material with all liftscomplete as per specifications iv) Dismantling wood work wrought framed and fixed in frames of trusses upto a Height of 5m above Plinth Level with all lead and lift and directions of the Engineer in charge of the work	Cum	460.00	Four Hundred Sixty Rupees and Zero Paise

19/7/16

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Signature of the Contractor

Executive Engineer (Project)

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
5	106.22	KSRRB M200-14.2.Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work B. In cement mortar. with all lead and lift and directions of the Engineer in charge of the work	Cum	320.00	Three Hundred Twenty Rupees and Zero Paise
6	65.54	KSRRB M200- 15.2. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications.Rubble stone masonry in cement mortar. with all lead and lift and directions of the Engineer in charge of the work	Cum	240.00	Two Hundred Forty Rupees and Zero Paise
7	187.61	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms).with all lead and lift and directions of the Engineer in charge of the work	Sqm	100.00	One Hundred Rupees and Zero Paise
8	522.17	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the exavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 with all lead and lift and directions of the Engineer in charge of the work	Cum	360.00	Three Hundred Sixty Rupees and Zero Paise
9	47.44	KSRB 2.8 : Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification. No. KBS with all lead and lift and directions of the Engineer in charge of the work	Cum	2100.00	Two Thousand One Hundred Rupees and Zero Paise
10	23.60	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation cement mortar 1:6, stone hammerddressed in courses not less than 20 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing completeas per specifications.KBS 5.1.13 with all lead and lift and directions of the Engineer in charge of the work	Cum	5200.00	Five Thousand Two Hundred Rupees and Zero Paise

Signature of the Contractor

Executive Engineer (Project)

Executive Engineer
Project Division
Yelahanka Zone
Bangalore
19/7/16

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
11	15.34	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6,edges of stone chistei dressed in courses not less than 15 cms high, bond stones at two m.apart in each course including cost of materials, labour, curing completeas per specifications.KBS 5.1.13 with all lead and lift and directions of the Engineer in charge of the work	Cum	5500.00	Five Thousand Five Hundred Rupees and Zero Paise
12	84.37	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8(M7.5)with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No. KBS 4.1, 4.2 with all lead and lift and directions of the Engineer in charge of the work	Cum	5850.00	Five Thousand Eight Hundred Fifty Rupees and Zero Paise
13	271.62	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. specification. No. KBS 2.9 with all lead and lift and directions of the Engineer in charge of the work	Cum	250.00	Two Hundred Fifty Rupees and Zero Paise
14	37.28	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300- 2 complete as per specifications.(which includes cost of gravel / murrum, watering charges & compaction by vibratory roller) MORTH Specification No. with all lead and lift and directions of the Engineer in charge of the work	Cum	420.00	Four Hundred Twenty Rupees and Zero Paise
15	200.10	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 with all lead and lift and directions of the Engineer in charge of the work	Sqm	240.00	Two Hundred Forty Rupees and Zero Paise

19/7/16

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Signature of the Contractor

Executive Engineer (Project)

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
16	100.99	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness , including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2 with all lead and lift and directions of the Engineer in charge of the work	Sqm	290.00	Two Hundred Ninety Rupees and Zero Paise
17	160.46	KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	380.00	Three Hundred Eighty Rupees and Zero Paise
18	147.28	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	380.00	Three Hundred Eighty Rupees and Zero Paise
19	376.14	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness 200 mm including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	300.00	Three Hundred Rupees and Zero Paise
20	387.78	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	310.00	Three Hundred Ten Rupees and Zero Paise
21	232.25	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specificaitons.-do- Ground floor Specification No. KBS 4.6.2 with all lead and lift and directions of the Engineer in charge of the work	Sqm	260.00	Two Hundred Sixty Rupees and Zero Paise
22	256.72	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	270.00	Two Hundred Seventy Rupees and Zero Paise
23	21.04	KSRB 4-6.11 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for Stairs (excluding landing) except spiral staircase including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	480.00	Four Hundred Eighty Rupees and Zero Paise
24	22.49	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	650.00	Six Hundred Fifty Rupees and Zero Paise

Executive Engineer
Project Division
Yelahanka Zone
Executive Engineer (Project)
Bangalore

Signature of the Contractor

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
25	28.40	KSRB 4-6.10 :Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc. , including edges including cost of all materials, labour complete as per specificaiton. Specification No. KBS 4.6.2 -do- Ground Floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	280.00	Two Hundred Eighty Rupees and Zero Paise
26	35.05	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	270.00	Two Hundred Seventy Rupees and Zero Paise
27	775.56	Providing and laying in Mat for RCC roof at below the steel for avoiding concrete cement slurry as per the requirement of with all lead and lift and directions of the Engineer in charge of the work	Sqm	60.00	Sixty Rupees and Zero Paise
28	154.19	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M25 with OPCcement @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cumn and fine aggregtes@ 0.47cum, with superplastisiser @3lts confirmingto IS9103-1999 reaffirmed 2008,machine mixed, concrete laid in layersnot exceeding 15 cms thick, vibrated for all work in foundation for fooiings,pedestals, retainingwalls, return walls, walls(any thickness) including attached plasters,columns, pillars, posts, struts, buttresses, bed blocks, anchor blocks, and plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No.KBS 4.1,4.6 with all lead and lift and directions of the Engineer in charge of the work	Cum	6500.00	Six Thousand Five Hundred Rupees and Zero Paise
29	41.28	KSRB 4.2.7 : Providing and laying in position reinforced cementconcrete of design mix M25 with OPC cement @ 340kgs, with 20mmand down size graded granite metal coarse aggregates @0.47 cum with superplastisiser @3lts confirming toIS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in ground floor level for roof slabs ,staircase, lintels , beams, retaining walls ,return wall, walls (an thick ness) including attached plasters,columns,pillars,posts,struts.butters,string or lacing courses,parapets,coping,bed blocks,anchor blocks,plain window cills,fillets including cost of all materials, labour,HOM of machinery, curing, complete as per specifications.Specification No. KBS 4.1, 4.6 -do- Ground Floor with all lead and lift and directions of the Engineer in charge of the work	Cum	7500.00	Seven Thousand Five Hundred Rupees and Zero Paise
30	49.36	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Cum	6300.00	Six Thousand Three Hundred Rupees and Zero

19/7/16

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

Signature of the Contractor

Executive Engineer (Project)

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
31	181.88	Providing and laying cement concrete using 20 mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar,with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges) Ready mixed cement for concrete for beams,staircase,and roof with M-25. with all lead and lift and directions of the Engineer in charge of the work	Cum	6400.00	Six Thousand Four Hundred Rupees and Zero Paise
32	22.94	KSRB 4.2.11 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 27.20kgs, with 12mm and down size graded granite metal coarse aggregates @0.5865cum and fine aggregtes @ 0.391cum, with superplastisiser @0.225lts, machine mixed, well compacted for plain chajja of 8.5 cms. average thickness, upto ground floor level, including cost of all materials, labour, HOM of machinery, finishing, curing, complete as per specifications. Specification No. KBS 4.1, 4.6 -do- Ground Floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	520.00	Five Hundred Twenty Rupees and Zero Paise
33	28.31	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	520.00	Five Hundred Twenty Rupees and Zero Paise
34	3.83	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20with OPCcement @ 320kgs, with 20mmand down size graded granite metal coarse aggregates @0.878cumandfineaggregtes@ 0.459cum, with superplastisiser @3lts confirmingto IS9103-1999Reaffirmed2008,machine mixed, concrete laid in layersnot exceeding 15 cms thick, vibrated for all work in foundation for fooiings,pedestals, retainingwalls, return walls, walls(any thickness) including attached plasters,columns, pillars, posts, struts, buttresses, bed blocks, anchor blocks, and plinths etc., including cost of all materials, labour, HOMof machinery, curing, complete as per specifications. with all lead and lift and directions of the Engineer in charge of the work	Cum	6000.00	Six Thousand Rupees and Zero Paise
35	33.98	KSRB 4.9.2 : Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Ton Kgs	68500.00	Sixty Eight Thousand Five Hundred Rupees and Zero Paise

Signature of the Contractor

Executive Engineer (Project)

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

19/7/16

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
36	17.44	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Tons Kgs	68900.00	Sixty Eight Thousand Nine Hundred Rupees and Zero Paise
37	332.89	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 35 N/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.-do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	900.00	Nine Hundred Rupees and Zero Paise
38	367.16	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	1000.00	One Thousand Rupees and Zero Paise
39	36.14	KSRB 5-15 : Providing and constructing non-load bearing wall with cement concrete solid blocks with compressive strength not less than 35 N/sqm with cement mortar 1:4 (Jamb, closer blocks) with blocks of size 40x10x20cms . (lxbxh) conforming to I.S : 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	700.00	Seven Hundred Rupees and Zero Paise
40	57.52	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	750.00	Seven Hundred Fifty Rupees and Zero Paise
41	386.61	KSRB15-3.8 : Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners, wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	200.00	Two Hundred Rupees and Zero Paise
42	429.40	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	200.00	Two Hundred Rupees and Zero Paise
43	386.61	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. -do- with primer -do- Ground floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	80.00	Eighty Rupees and Zero Paise
44	429.40	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	85.00	Eighty Five Rupees and Zero Paise

Executive Engineer
Project Division
Yelahanka Zone
Bangalore

19/7/16

Signature of the Contractor G. Gopi Reddy

Executive Engineer (Project)

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
45	15.00	KSRB 9-27.1 : Fixing of door frames in an exisying opening including embedding frame in floor and walls after cutting masonary for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and downsize granite metal painting two coats of coal tar to sides of frame,making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour, complete as per specifications. with all lead and lift and directions of the Engineer in charge of the work	Nos	1000.00	One Thousand Rupees and Zero Paise
46	0.70	KSRB 9.4-2: Providing Honne wood frames of doors, windows, clerestory windows,ventilators and other frames , wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps),but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 with all lead and lift and directions of the Engineer in charge of the work	Cum	128790.00	One Hundred Twenty Eight Thousand Seven Hundred Ninety Rupees and Zero Paise
47	25.08	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 30mm. thick with bottom and lockrails 180mm wide top rail and styles 100mm wide as per drawing andpanels of 25mm thick including cost of materials, labour, HOM ofmachineries complete as per specifications. (excluding cost of fixtures) with all lead and lift and directions of the Engineer in charge of the work	Cum	3500.00	Three Thousand Five Hundred Rupees and Zero Paise
48	830.34	Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods,or combination of M.S. flats and square rods as per approved design,drawing including cutting steel sections and welding the same torequired pattern with a coat of red lead primer, cost of materials, fixtures,labour and HOM of machinery complete as per specifications with all lead and lift and directions of the Engineer in charge of the work -do- Ground floor	Sqm	86.76	Eighty Six Rupees and Seventy Six Paise
49	1291.92	do-First floor with all lead and lift and directions of the Engineer in charge of the work	Sqm	140.00	One Hundred Forty Rupees and Zero Paise
50	4.00	KSRB 12-6.1 : Providing 20mm square M.S footrest and fixing in manhole Nos 232.00 with M 10 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS 12.4.6 with all lead and lift and directions of the Engineer in charge of the work	Nos	270.00	Two Hundred Seventy Rupees and Zero Paise

Executive Engineer
Project Division
Yelahanka Zone
Bangalore
19/7/16

Signature of the Contractor

Executive Engineer (Project)

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
51	48.52	KSRB 8.6-5 : Providing and fixing on wall surface 2.5 kg / sq.cm H.D.P.E. rain down water pipes 110 mm outer dia approved make and brand with necessary specials like shoes, bends and offsets fixed with iron clamps, wall plugs, screws, including cost of materials, labour, curing complete as per specifications with all lead and lift and directions of the Engineer in charge of the work	M	500.00	Five Hundred Rupees and Zero Paise
52	124.10	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching , refilling & testing of joints complete. (external work). 25mm nominal OD pipes. with all lead and lift and directions of the Engineer in charge of the work	M	170.00	One Hundred Seventy Rupees and Zero Paise
53	3.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer in charge of the work	Nos	620.00	Six Hundred Twenty Rupees and Zero Paise
54	100.00	Providing and fixing to wall, ceiling and floor, medium densitypolyethylene pipes 6.00 kgf/sq.cm working pressure 140mm outsidediameter with special flange, compression type fittings, wall clips, makinggood the wall, ceiling and floor, including cost of all materials, labourcharges, HOM of equipments and testing complete as per specifications with all lead and lift and directions of the Engineer in charge of the work	Sqm	560.00	Five Hundred Sixty Rupees and Zero Paise
55	2.00	Providing and placing on terrace, polyethylene waterstorage tanks with manhole lid and suitable locking arrangements,making holes of suitable diameter for inlet, outlet and over flow pipes,including cost of all materials, labour, transport charges, HOM ofequipments and testing complete as per specifications.(For 1000 litre capacity) with all lead and lift and directions of the Engineer in charge of the work	Ltr	8850.00	Eight Thousand Eight Hundred Fifty Rupees and Zero Paise
56	6.00	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).12.113.1 -do- 10cms x 7.5cms with all lead and lift and directions of the Engineer in charge of the work	Nos	260.00	Two Hundred Sixty Rupees and Zero Paise

Executive Engineer
Project Division
Executive Engineer (Project)
Bangalore

19/7/16

Signature of the Contractor

Name of the Firm				Approved Teneder Rates of K Gopi Reddy	
Sl. No.	App Qty	Description	Unit	Rate in figures	Rate in words
57	2.00	KSRB13-6.4-2 : Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 25mm dia nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS with all lead and lift and directions of the Engineer in charge of the work	Each	630.00	Six Hundred Thirty Rupees and Zero Paise
58	5.00	KSRB 12-8.1 : Constructing brick masonry inspection chamber 455x610mm, and 450mm depth , (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications. Specification No. KBS with all lead and lift and directions of the Engineer in charge of the work	Each	6830.00	Six Thousand Eight Hundred Thirty Rupees and Zero Paise
59	1.00	KSRB13-5 : Providing and fixing water meter with stop cock, jam nut, socket in G.I pipe line including cutting and threading the pipe and making long screws including cost of all materials, labour, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.19 / 13.16 with all lead and lift and directions of the Engineer in charge of the work	Set	1370.00	One Thousand Three Hundred Seventy Rupees and Zero Paise
60	1.00	Providing ,supplying & commissionig of 1.0H.P/75 kW (submersible single phase pump)of ATLANTA/SUGUNA/CRI/KIRLOSKAR/OTHER EQUALENT PUMPS with all lead and lift and directions of the Engineer in charge of the work	Nos	12660.00	Twelve Thousand Six Hundred Sixty Rupees and Zero Paise
61	271.62	Conveying the excavated debries and over burden earth etc to a lead 20 kms distances by using private vehicles this including the cost of loading and inloading charges etc with all lead and lift and directions of the Engineer in charge of the work	Cum	120.00	One Hundred Twenty Rupees and Zero Paise

Signature of the Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

19/7/14

Executive Engineer
Project Division
Yelahanka Zone
Bangalore